

# Baling Contractors

To ensure buyers are provided with consistent, premium quality, it's essential that all crop is full senesced and meets moisture specification before baling. To this end, we suggest that contractors visibly inspect cut crop on arrival so they are confident that it is ready for baling before starting out.

EQUIPMENT SHOULD BE SET UP TO PRODUCE FULL HESSTON BALES  
(TARGET BALE WEIGHT 600KG) THAT MEET TERRAVESTA'S SPECIFICATIONS:

